
Potrero Power Plant -Offshore Sediment Area Remediation Project

Bay Conservation and Development Commission

Commission Hearing on M2017.05-003

21 February 2019

Potrero Power Plant – Areas of Concern



Inter-Agency Permitting Process

- Early Buy-in on Remedial Design
- Collaborative Inter-Agency Process

• CEQA and RAP Approval Water Quality Water Certification Board • NWP 38 to Dredge (in Army Waters of the U.S.) Corps • Consultation (for activities in Waters of the State) **CDFW** • License and Access Agreements Port of SF Permit to Fill the Bay **BCDC**

Inter-Agency Group Begun Working in 2009

- Water Board
- Port of SF
- EPA
- BCDC
- CDFW
- NOAA/NMFS
- USACE
- SFDPH

Site History - Over a Century of Industrial Activity





Above - MGP Operations in the early 1900s

Below – Former Power Plant and Revetment Area (foreground)



- 1872 to 1930 –
 Historical fill
- PG&E operated MGP 1906 to 1930
- 1883 to 1950 Sugar Refining
- 1910 to 1960s –
 Station A Power
 Generation
- 1965 to 2011 Power Plant Unit 3 Operations
- 1999 PG&E sold the Power Plant

Remedial Action Objectives


- Mitigate the potential for exposure of fish to PAHs that bioaccumulate in sediment organisms at concentrations greater than in the Ambient Area organisms
- Mitigate potential future exposure of humans to impacted sediment within areas accessible to wading




Remnant of Spreckle's Sugar Refinery Wharf

Remediation Activities

Dredge Areas



Cap/In Situ/MNRA Areas



- Dredge and Cap by Segment
 - Segment 1 ~ 2 to 3 ft over 20,324 SF
 - Segment 2 ~5 to 7 ft over 31,278 SF
 - Segment 3 ~2 to 3 ft
 over 12,357 SF
- In Situ Treatment
 - Addition of activated carbon amendment of less than 2-in thickness over 74,275 SF
- Monitored Natural Recovery/Attenuation
 - Allow natural capping in Cell 16 over 18,731 SF

Project Implementation

- Work Window June 1 to Nov 30
 - 2019 Construction Window
- Resource Monitoring During Construction
 - Turbidity controls and water quality monitoring
- Long term Monitoring RRMP
 - Cap stability and erosion
 - MNR/A progress
 - In situ treatment and MNR/A monitoring for bioaccumulation



Use of environmental bucket within turbidity curtains

Project Benefits



- Overall Net Benefit to the Environment
- No Net Fill
- Minimizes disturbance of health benthic communities
- Cap design promotes natural depositional processes and recolonization of native benthic organisms
- Reduces risk to future shoreline users
- Allows for future shoreline improvements

THANK YOU

Q&A