



State Route 37 Sears Point to Mare Island Improvement Project Presenting to the San Francisco Bay Conservation Commission Engineering Criteria Review Board May 21, 2025





Introductions

Caltrans:

- Javier Mendivil, PM
- Michael Bergman, Bridge Design
- Lewis Shen, Bridge Design
- Olivier Mbatchou, Roadway Design
- John Moore, Geotech
- Peter Wei, Geotech
- Jinpeng Li, Hydraulics
- Skylar Nguyen, Env Planning
- David Weber, Biology

Metropolitan Transportation Commission

- Kevin Chen – Assistant Director
- Jeanette Weisman – SR 37 Corridor Program Manager

AECOM Consultant Team

- Gary Sjelin, Hydraulics
- Brad Mays, Drainage
- Dillon Lennebacker, Environmental
- Joy Villafranca, Project Engineering Manager

Presentation Overview

- Project Overview
- Purpose and Need
- Proposed Elements in BCDC Jurisdiction
- General Overview
- Technical Discussion

Phased Implementation

Environmental - Design - Construction

Sears Point to Mare Island Improvement

- Equity
 - *Improve Travel Times and Reliability
 - *Support Transit and Rideshare
 - *Public Access
- Baylands Restoration
- Resilience

Early Benefits



Transition

SR 37 Sea Level Rise Adaptation (I-80 – US 101)

- Long Term Corridor Resilience (Planning and Environmental Linkages Study)
- Multiple Project Implementation (Flood Reduction Project – 101 to Atherton)
- Equity, Bike, Pedestrian, Transit, and Public Access
- Advance Mitigation

RESILIENTSR37



Today

2029

2040

2050

Project Location, Purpose, and Need

Location:

- Sonoma County
SR 37 (PM 2.6 to 4.9) and
SR 121 (PM 0 to 0.3)

Purpose:


- Improve traffic flow

Need:

- Address recurring congestion

Minimization:


- Create waters/habitat
- Accommodate tidal prism




Project Components in BCDC


Project Elements

- Within BCDC Certain Waterway Jurisdiction
 - Tolay Creek Bridge Replacement
 - Retaining Walls 3 and 4
 - Fill Removal (creation of new waters from uplands)



 Study Area

Potential BCDC Jurisdiction Feature

 Certain Waterway



Tolay Creek Bridge Replacement

Existing



New Bridge





Tolay Creek Bridge - Replacement Configuration


Existing Tolay Creek Bridge



Existing Bridge:

Single span, Br Length = 61ft


Proposed Bridge



Proposed Bridge Replacement:


6 spans, Br Length = 375ft

Tolay Creek Bridge – Span Configuration




- Precast/prestressed voided slab w/ CIP deck continuous superstructure.
- Drop Bentcap on Pile Extensions. Additional bentcap width added to support the superstructure during fault rupture.

Tolay Creek Bridge – Plan View



Tolay Creek Br – Typical Section/Stage Construction



Stage 1 Construction:


- Temp Traffic Detour with Temp Bridge over exist Tolay Crk
- Constructing partial new Tolay Crk Br to the South.

Stage 2 Construction:

- Traffic on newly constructed partial Tolay Crk Br to the south.
- Construct partial Tolay Crk Br to the North.


Retaining Walls – Typical Section

Retaining Wall 3



SECANT PILE WALL
TYPICAL SECTION
1/4" = 1'-0"

Retaining Wall 4, 5



RETAINING WALL TYPE 1 (Mod)
TYPICAL SECTION
1" = 5'

DESIGN GENERAL NOTES

TOLAY CREEK BRIDGE

Design

- AASHTO LRFD Bridge Design Specs 2017, with CA Amendments updated June 2024
- Standard Plans and Specs, 2024 with Revised Standard Plans April 2025

Seismic Design

- Caltrans Seismic Design Criteria, Version 2.0, April 2019

Fault Rupture: (Static Offset)

- Horizontal Design Offset = 1.7 feet
- Vertical Design Offset = 0.9 feet

Dead Load

- Includes 1" Polyester overlay

Live Loading

- HL93 and permit design load

RETAINING WALLS 3, 4 & 5

Design

- AASHTO LRFD Bridge Design Specs 2017, with CA Amendments updated June 2024
- Standard Plans and Specs, 2024 with Revised Standard Plans April 2025


Soil Parameters (Lightweight EPS block)

- $\Phi = 27^\circ$
- $\gamma = 35$ pcf
- $K_n = 0.35$
- $K_v = 0$
- $K_\alpha = 0.38$

TEMPORARY BRIDGE STRUCTURE



Example of one type, Acrow Br Co.
Temporary bridge type will be
selected by the Construction
Contractor



Tolay Creek Bridge – Geotechnical Investigation




Tolay Creek - Geotechnical Investigation

Field investigation from 2023 to 2025

- Four mud rotary wash soil borings up to 161.5 feet in depth
- Field testing included standard penetration testing (SPT) and pocket penetration testing (PP) during drilling
- Eight cone penetration testing (CPT) up to 119 feet in depth
- Three seismic measurements during CPT pushing
- A review of five As-built log of test borings (LOTB) drilled in 1973



Tolay Creek - Geotechnical Investigation



BENCHMARK

BM xxxx # Elev xx.x
xxxxxx
N xxxx
E xxxx
Vert: NAVDxx
Horiz: NADxx (xxxx)

CHECK PRINT
by _____

DRAFT

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
			X		
REGISTERED GEOTECHNICAL ENGINEER			DATE		
PLANS			APPROVAL DATE		
THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.					

REGISTERED PROFESSIONAL ENGINEER

Haoil Wei


No. 2922

Exp. 02-30-2026

GEOTECHNICAL

STATE OF CALIFORNIA

This LOTB sheet was prepared in accordance with the Caltrans Soil & Rock Logging, Classification, and Presentation Manual (2022 Edition).




PROFILE
Vert: 1" = 10'

GEOTECHNICAL SERVICES			STATE OF CALIFORNIA DEPARTMENT OF TRANSPORTATION		DIVISION OF ENGINEERING SERVICES BRIDGE DESIGN BRANCH X		TOLAY CREEK BRIDGE (REPLACE) LOG OF TEST BORINGS 1 OF 9	
FUNCTIONAL SUPERVISOR: J. C. Moore	DRAWN BY: S. Yang	FIELD INVESTIGATION BY: P. Wei/C. McMahon/M. Farrell	DATE PLOTTED => 28-MAR-2025	TIME PLOTTED => 10:25	ORIGINAL SCALE IN INCHES FOR REDUCED PLANS	UNIT: 6650	BRIDGE No. 20-0090	
CHECKED BY: X			FILE => %c.b. (replace)_lotb1of9.dgn	USERNAME => #161293	PROJECT NUMBER & PHASE: 0419000255-1	POST MILE 4.04	CONTRACT No. 04-107614	
005 CIVIL LOG OF TEST BORINGS SHEET (ENGLISH) (REVISION 6/5/2023)			DISREGARD PRINT EARLIER REVISION			REVISION DATES 3-16-25		
						SHEET OF X X		

```
BM xxxx #      Elev xx.x
xxxxxx
N xxxx
E xxxx
Vert: NAVDxx
Horiz: NADxx (xxxx)
```

DRAFT

This LOTB sheet was prepared in accordance with the Caltrans Soil & Rock Logging, Classification, and Presentation Manual (2022 Edition).



PROFILE
Vert: 1" = 10'

GEOTECHNICAL SERVICES FUNCTIONAL SUPERVISOR: J. C. Moore DRAWN BY: S. Yang FIELD INVESTIGATION BY: P. Wei/C. McMahon/W. Farrell CHECKED BY: X										STATE OF CALIFORNIA DEPARTMENT OF TRANSPORTATION DIVISION OF ENGINEERING SERVICES BRIDGE DESIGN BRANCH X										BRIDGE No. 20-0090 POST MILE 4.04 TOLAY CREEK BRIDGE (REPLACE) LOG OF TEST BORINGS 2 OF 9																			
OGS CIVIL LOG OF TEST BORINGS SHEET (ENGLISH) (REVISION 6/5/2023)										DATE PLOTTED => 28-MAR-2025 TIME PLOTTED => 10:25 FILE => .c.b. (replace).lbt2of9.dgn USERNAME => s161293										ORIGINAL SCALE IN INCHES FOR REDUCED PLANS 0 1 2 3 UNIT: 8650 PROJECT NUMBER & PHASE: 0419000255-1 COUNTY/ROUTE/ZONE: Son/37/2 CONTRACT No.: 04-107614										DISREGARD PRINT BEARING EARLIER REVISION DATES 3-16-25 REVISION DATES SHEET OF X X									

BENCHMARK

BM xxxx # Elev xx.x
XXXXXX
N XXXX
E XXXX
Vert: NAVDxx
Horiz: NADxx (xxxx)


CHECK PRINT
by _____

DRAFT

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS

REGISTERED GEOTECHNICAL ENGINEER DATE _____ X
Haoil Wei
No. 2492
Exp. 09-30-2026
PLANS APPROVAL DATE _____
THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS
SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR
COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

This LOTB sheet was prepared in accordance with the Caltrans Soil & Rock Logging, Classification, and Presentation Manual (2022 Edition).



01-04-23
Terminated at Elev -100.0
ER = 81%

NOTE:
Groundwater was not measured
in boring R-23-001 due to mud
rotary drilling method.

PROFILE
Vert: 1" = 10'

GEOTECHNICAL SERVICES

FUNCTIONAL SUPERVISOR: J. C. Moore

DRAWN BY: S. Yang

FIELD INVESTIGATION BY: P. Wei/C. McMahon/W. Farrell

CHECKED BY: X

STATE OF
CALIFORNIA
DEPARTMENT OF TRANSPORTATION

DIVISION OF ENGINEERING SERVICES
BRIDGE DESIGN
BRANCH X

BRIDGE No.
10-0090
POST MILE
4.04

OLAY CREEK BRIDGE (REPLACE)
LOG OF TEST BORINGS 3 OF 9

005 CIVIL LOG OF TEST BORINGS SHEET
(ENGLISH) (REVISION 6/9/2023)

DATE PLOTTED => 28-MAR-2025 TIME PLOTTED => 10:25
FILE => t.g.d. (replace)...logb3of9.dgn USERNAME => s161293

ORIGINAL SCALE
IN INCHES FOR
REDUCED PLANS 0 1 2 3

UNIT: 3650
PROJECT NUMBER & PHASE: 0419000255-1
COUNTY/ROUTE/ZONE: Son/37/2
CONTRACT No.: 04-107614

DISCARD PRINTS BEARING
EARLIER REVISION DATES

REVISION DATES
SHEET OF
X X

BENCHMARK


BM xxxx # Elev xx.x
xxxxxx
N xxxx
E xxxx
Vert: NAVDxx
Horiz: NADxx (xxxx)

CHECK PRINT
by _____

DRAFT

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
REGISTERED GEOTECHNICAL ENGINEER			DATE		
Haoil Wei			2922		
PLANS			APPROVAL DATE		
THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.			GEOTECHNICAL STATE OF CALIFORNIA		

This LOTB sheet was prepared in accordance with the Caltrans Soil & Rock Logging, Classification, and Presentation Manual (2022 Edition).



GEOTECHNICAL SERVICES

FUNCTIONAL SUPERVISOR: J. C. Moore

DRAWN BY: S. Yang

FIELD INVESTIGATION BY: P. Wei/C. McMahon/M. Farrell

CHECKED BY: X

STATE OF
CALIFORNIA
DEPARTMENT OF TRANSPORTATION

DIVISION OF ENGINEERING SERVICES
BRIDGE DESIGN
BRANCH X

BRIDGE No.
20-0090
POST MILE
4.04

TOLAY CREEK BRIDGE (REPLACE)
LOG OF TEST BORINGS 4 OF 9

005 CIVIL LOG OF TEST BORINGS SHEET
(ENGLISH) (REVISION 6/5/2023)

DATE PLOTTED => 28-MAR-2025 TIME PLOTTED => 10:25
FILE => *.c.b. (replace)_lotb4of9.dgn USERNAME => sl61293
ORIGINAL SCALE
IN INCHES FOR
REDUCED PLANS 0

UNIT: 8650
PROJECT NUMBER & PHASE: 0419000255-1

COUNTY/ROUTE/ZONE: Son/37/2
CONTRACT No.: 04-107614

DISREGARD PRINT
EARLIER REVISION DATES

REVISION DATES
3-16-25
SHEET OF
X X


```
BM xxxx #      Elev xx.x
xxxxxx
N xxxx
E xxxx
Vert: NAVDxx
Horiz: NADxx (xxxx)
```

CHECK PRINT
by _____

Dist.	COUNTY	ROUTE	POST MILES	TOTAL PROJECT	SHEET No.	TOTAL SHEETS

X
DATE _____


REGISTERED GEOTECHNICAL ENGINEER



PLANS APPROVAL DATE _____

THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS
 SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR
 COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

-10



01-24-24
Terminated at Elev 151.5
ER_i = 95%

NOTE:
Groundwater was not measured in boring
R-24-005 due to mud rotary drilling method.

PROFILE
Vert: 1" = 10'

GEOTECHNICAL SERVICES										STATE OF CALIFORNIA DEPARTMENT OF TRANSPORTATION										DIVISION OF ENGINEERING SERVICES BRIDGE DESIGN BRANCH X										BRIDGE No. 20-0090 POST MILE 4.04										TOLAY CREEK BRIDGE (REPLACE) LOG OF TEST BORINGS 5 OF 9																																							
FUNCTIONAL SUPERVISOR: J. C. Moore										DRAWN BY: S. Yang CHECKED BY: X										FIELD INVESTIGATION BY: P. Wei/C. McMahon/M. Farrell																																																											
ODS CIVIL LOG OF TEST BORINGS SHEET (ENGLISH) (REVISION 6/5/2023)										DATE PLOTTED => 28-MAR-2025 TIME PLOTTED => 10:25 FILE => "c.b. (replace).lotr5of9.dgn USERNAME => s161293										ORIGINAL SCALE IN INCHES FOR REDUCED PLANS 0										UNIT: P650 PROJECT NUMBER & PHASE: 0419000255-1										COUNTY/ROUTE/ZONE: Son/37/2 CONTRACT No.: 04-107614										DISREGARD PRINTS EARLIER REVISION DATES										BEARING DATES										SHEET 08 3-18-15 X X									

BENCHMARK


BM xxxx # Elev xx.x
xxxxxx
N xxxx
E xxxx
Vert: NAVDxx
Horiz: NADxx (xxxx)

DRAFT

CHECK PRINT
by _____

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
REGISTERED GEOTECHNICAL ENGINEER			DATE		
Haoil Wei			No. 2922		
PLANS APPROVAL DATE			Exp. 02-30-2026		
THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.					

This LOTB sheet was prepared in accordance
with the Caltrans Soil & Rock Logging,
Classification, and Presentation Manual
(2022 Edition).



01-08-25
Terminated at Elev 151.5
ER = 95%

NOTE:
Groundwater was not measured in boring
R-25-006 due to mud rotary drilling method.

PROFILE
Vert: 1" = 10'

GEOTECHNICAL SERVICES

FUNCTIONAL SUPERVISOR: J. C. Moore

DRAWN BY: S. Yang

FIELD INVESTIGATION BY: P. Wei/C. McMahon/M. Farrell

CHECKED BY: X

STATE OF
CALIFORNIA
DEPARTMENT OF TRANSPORTATION

DIVISION OF ENGINEERING SERVICES
BRIDGE DESIGN
BRANCH X

BRIDGE No.
20-0090
POST MILE
4.04

TOLAY CREEK BRIDGE (REPLACE)
LOG OF TEST BORINGS 6 OF 9

005 CIVIL LOG OF TEST BORINGS SHEET
(ENGLISH) (REVISION 6/5/2023)

DATE PLOTTED => 28-MAR-2025 TIME PLOTTED => 10:25
FILE => *.cub (replace).lotb609.dgn USERNAME => b161293
ORIGINAL SCALE
IN INCHES FOR
REDUCED PLANS 0

UNIT: 8650
PROJECT NUMBER & PHASE: 0419000255-1
COUNTY/ROUTE/ZONE: Son/37/2
CONTRACT No.: 04-107614

DISREGARD PRINT
EARLIER REVISION

REVISION DATES
3-10-25
SHEET OF
X X

BENCHMARK

BM xxxx # Elev xx.x
xxxxxx
N xxxx
E xxxx
Vert: NAVDxx
Horiz: NADxx (xxxx)

DRAFT

CHECK PRINT
by _____

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS


REGISTERED GEOTECHNICAL ENGINEER DATE _____ X

PLANS APPROVAL DATE _____

THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

REGISTERED PROFESSIONAL ENGINEER
Haoil Wei
No. 2922
Exp. 02-30-2026
GEOTECHNICAL
STATE OF CALIFORNIA

This LOTB sheet was prepared in accordance with the Caltrans Soil & Rock Logging, Classification, and Presentation Manual (2022 Edition).



PROFILE
Vert: 1" = 10'

GEOTECHNICAL SERVICES			STATE OF CALIFORNIA DEPARTMENT OF TRANSPORTATION		DIVISION OF ENGINEERING SERVICES BRIDGE DESIGN BRANCH X		TOLAY CREEK BRIDGE (REPLACE) LOG OF TEST BORINGS 7 OF 9					
FUNCTIONAL SUPERVISOR: J. C. Moore	DRAWN BY: S. Yang	FIELD INVESTIGATION BY: P. Wei/C. McMahon/M. Farrell	DATE PLOTTED => 28-MAR-2025	TIME PLOTTED => 10:25	ORIGINAL SCALE IN INCHES FOR REDUCED PLANS	BRIDGE No. 20-0090	POST MILE 4.04	COUNTY/ROUTE/ZONE: Son/37/2	DISREGARD PRINT EARLIER REVISION	REVISION DATES	SHEET OF	
CHECKED BY: X			FILE => %c.b. (replace)_lotb7of9.dgn USERNAME => #161293			PROJECT NUMBER & PHASE: 0419000255-1		CONTRACT No.: 04-107614		3-18-25	X	X

BENCHMARK


BM xxxx # Elev xx.x
xxxxxx
N xxxx
E xxxx
Vert: NAVDxx
Horiz: NADxx (xxxx)

CHECK PRINT
by _____

DRAFT

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
REGISTERED GEOTECHNICAL ENGINEER			DATE		
Haoil Wei			2922		
PLANS			APPROVAL DATE		
THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.			EXP 02-30-2026		

This LOTB sheet was prepared in accordance with the Caltrans Soil & Rock Logging, Classification, and Presentation Manual (2022 Edition).



PROFILE
Vert: 1" = 10'

GEOTECHNICAL SERVICES			STATE OF CALIFORNIA DEPARTMENT OF TRANSPORTATION		DIVISION OF ENGINEERING SERVICES BRIDGE DESIGN BRANCH X		TOLAY CREEK BRIDGE (REPLACE) LOG OF TEST BORINGS 8 OF 9				
FUNCTIONAL SUPERVISOR: J. C. Moore	DRAWN BY: S. Yang	FIELD INVESTIGATION BY: P. Wei/C. McMahon/M. Farrell	DATE PLOTTED => 28-MAR-2025	TIME PLOTTED => 10:25	ORIGINAL SCALE IN INCHES FOR REDUCED PLANS	UNIT: 8650 PROJECT NUMBER & PHASE: 0419000255-1	COUNTY/ROUTE/ZONE: Son/37/2 POST MILE 4.04	DISREGARD PRINT EARLIER REVISION	REVISION DATES 3-16-25	SHEET X	OF X

DRAFT

DIST.	COUNTY	ROUTE	POST MILE-TOTAL PROJECT	SHEET NO.	TOTAL SHEETS
04	SON	37			
CERTIFIED ENGINEERING GEOLOGIST					NUMBER
DATE APPROVED					



BM "R-1"-PAINTED USC&GS BM

chisled "D" in PCC base telephone booth (NW corner). 97' R+ Rte 37 "R+ LOL" 236+25 ELEV. 11.87


DIVISION OF ENGINEERING SERVICES - GEOTECHNICAL SERVICES
As-Built Log of Test Borings sheet is considered an informational document only. As such, the State of California registration seal with signature, license number and registration certificate expiration date confirm that this is a true and accurate copy of the original document. It does not attest to the accuracy or validity of the information contained in the original document. This drawing is available and presented only for the convenience of any bidder, contractor or other interested party.

DIST.	COUNTY	ROUTE	POST MILE-TOTAL PROJECT	SHEET No.	TOTAL SHEETS
04	SON	37			

REGISTERED PROFESSIONAL GEOLOGIST		DATE	
TOLAY CREEK BRIDGE (REPLACE)			
LOG OF TEST BORINGS 9 OF 9			
UNIT:	3650	CONTRACT No.	BRIDGE No.
PROJ. No. & PHASE:	0419000255-1	04-107614	20-0090
AS-BUILT VERT DATUM: NGVD29 CONVERSION: NAVD83-NGVD29+2.66'		Sheet of	
NOTE: A COPY OF THIS LOG OF TEST BORINGS IS AVAILABLE AT OFFICE OF STRUCTURE MAINTENANCE AND INVESTIGATIONS, SACRAMENTO, CALIFORNIA			



PLAN
SCALE 1"=50'



PROFILE

SCALE: 1"=10'
Note: Plan & Profile of structure obtained from General Plan dated 11-12-73

ENGINEERING GEOLOGY SECTION

PIELD STUDY	BY R. FOX	6-25-73	Approval Recommended By
DRAWN	BY DERANIA	7-1-73	
CHECKED	BY R. FOX	7-6-73	

State of California
DEPARTMENT OF TRANSPORTATION

BRIDGE DEPARTMENT
DESIGN SECTION

BRIDGE NO.	20-8045
POST MILE	14.0


TOLAY CREEK BRIDGE
LOG OF TEST BORINGS



Tolay Creek - Geotechnical Investigation

04-1Q761/1Q76U

Ground Surface at Boring/CPT Locations and Approx. Bottom of Young Bay Mud



Tolay Creek - Geotechnical Investigation

Laboratory Testing included:

- Moisture content
- Particle gradation
- Atterberg limits
- Unconfined compression
- Consolidation
- Consolidated undrained triaxial
- Corrosion



Tolay Creek - Geotechnical Investigation

Subsurface conditions

- Fill thickness including AC/AB sections from 3 to 10 feet
- Very soft to soft clayey soils (young bay mud) from 34 to 60 feet in thickness
- Young bay mud thickness increases from west to east
- Stiff to hard clayey soils with a few layers of medium dense to very dense sand (consolidated bay mud) below young bay mud up to maximum depths drilled

Tolay Creek Bridge – Hydraulics




Figure 29. Tolay Creek Bridge (Existing Condition, Looking Downstream)

- Hydraulic study and report were prepared for the bridge
- HEC-RAS was used to develop a 2D model of the bridge
- HEC-RAS 2D hydrodynamic model was run for 12 scenarios developed from criteria in the Caltrans Highway Design Manual




Figure 30. Tolay Creek Bridge (Proposed Condition, Looking Downstream)



Sea Level Rise Considerations

Current OPC Guidance (2024)

- 0.8 to 1.3 Feet of SLR by 2050

Project Assumptions

- 9.9 feet 100-year maximum water surface elevation
- 1 foot wave crest
- 0.7 Feet of SLR by 2046
- 1 foot of freeboard
- Minimum Soffit elevation 12.6 feet

TABLE 6. Sea Level Scenarios for San Francisco.

Median values of Sea Level Scenarios, in feet, for each decade from 2020 to 2150, with a baseline of 2000. All median scenario values incorporate the local estimate of vertical land motion.

YEAR	LOW	INT-LOW	INTERMEDIATE	INT-HIGH	HIGH
2020	0.2	0.2	0.2	0.3	0.3
2030	0.3	0.4	0.4	0.4	0.4
2040	0.4	0.5	0.6	0.7	0.8
2050	0.5	0.6	0.8	1.0	1.3
2060	0.6	0.8	1.1	1.5	2.0
2070	0.7	1.0	1.4	2.2	2.9
2080	0.8	1.2	1.8	3.0	4.1
2090	0.9	1.4	2.4	3.8	5.3
2100	1.0	1.6	3.1	4.8	6.5
2110	1.0	1.8	3.8	5.6	7.8
2120	1.1	2.0	4.4	6.4	9.0
2130	1.2	2.2	4.9	7.0	9.9
2140	1.3	2.4	5.4	7.6	10.8
2150	1.3	2.6	6.0	8.1	11.7




Tolay Creek Bridge – Design Criteria/Model Assumptions


Table 7. Future Condition Model Scenarios

Scenario	Event Frequency	Precipitation Frequency	Tide at Peak Flow
9	100-Year	100-Year	MSL (3.70 Ft + 2.00 Ft Surge + 0.70 Ft SLR)
10	100-Year	50-Year	MHHW (6.42 Ft + 2.00 Ft Surge + 0.70 Ft SLR)
11	100-Year	No Precipitation	EHW (7.12 Ft + 2.00 Ft Surge + 0.70 Ft SLR)
12	50-Year	50-Year	MSL (3.70 Ft + 2.00 Ft Surge + 0.70 Ft SLR)

- The table outlines the most conservative modeling scenarios for the SR-37 Tolay Creek Bridge, incorporating a planning horizon of 2046 with a sea level rise (SLR) of 0.7 feet based on the 2024 California guidance.
- Scenarios include a range of precipitation frequencies combined with tidal conditions adjusted for surge and SLR.
- Tidal levels at peak flow are set at Mean Sea Level (MSL), Mean Higher High Water (MHHW), and Extreme High Water (EHW), each with a 2-foot surge and 0.7-foot SLR added.
- These assumptions reflect a conservative approach to account for future climate impacts and tidal influences on the hydraulic design of the proposed bridge.

SLR Considerations





Results

Part 3 – Issues and Applications in Coastal Highway Design

HEC-25 3rd ed.




Figure 11.16. Definition sketch of wave parameters and water levels for determining elevation of bridge deck for clearance from wave crests

Part 3 – Issues and Applications in Coastal Highway Design

HEC-25 3rd ed.




Figure 11.11. Schematic of resultant wave-induced load, with both uplift and lateral components, on a bridge deck




Figure 11.12. Schematic of typical time-history of wave loads on rigid structures

Results

Table 10. Future Condition Scenario Results

Scenario	Event Frequency (Years)	East Branch Maximum Discharge (cfs)	Tolay Bridge Maximum Discharge (cfs)	Maximum Water Surface (feet, NAVD 88)	Maximum Velocity (feet per second)
9	100	-19/+371	-136/+530	+8.95	1.2
10	100	-6/+289	-140/+408	+8.97	1.0
11	100	-21/+28	-332/+49	+9.45	0.7
12	50	-19/+286	-135/+422	+8.73	1.1

- The most conservative result is from Scenario 11, occurring during an extreme high water tide cycle.
- Maximum discharge through the Tolay Creek Bridge -332 cfs (upstream) and +49 cfs (downstream) in Scenario 11, reflecting significant tidal influence.
- The maximum velocity of 1.2 feet per second is observed in Scenario 9, aligning with a 100-year precipitation event and MSL tide conditions with surge and SLR.
- These results suggest lower flow rates and velocities compared to previous studies, attributed to reduced SLR assumptions (0.7 ft vs. 1.7 ft) and storage effects in the upstream marsh.
- The recommended minimum soffit elevation of +12.60 feet (NAVD 88) accounts for the +9.90 ft EHW, 1 ft wave crest, 0.7 ft SLR, and 1 ft freeboard, ensuring safety against future conditions.



Thank you!